



CAMEX EQUIPMENT IS PLEASED TO PROVIDE A QUOTATION ON A 125 BBL TANK (TRUCK MOUNTED) BRIEFLY DESCRIBED AS:

TANK:

ONE- ADVANCE 125 BBL STEEL TANK - CRUDE

CAPACITY:

125 BBL/ONE COMPARTMENT 20,000 L

PRODUCT:

PLACARD 1203

DENSITY:

2.2 LBS/L

WORKING PRESSURE:

ATMOSPHERIC

MAX TEMPERATURE:

90 DEGREES C

DESIGN PRESSURE:

3.3 PSIG MAWP

TEST PRESSURE:

5.0 PSIG

CODE:

TC406 CRUDE

TANK COMPONENTS:

| | |
|-------------------------|---|
| TYPE: | MILD STEEL CONSTRUCTION A HOT ROLLED |
| HEAVY BOTTOM: | 1/4" THICKNESS A36 HOT ROLL OVERLAPS 2 1/2" PER SIDE |
| UPPER SHELL: | 10 GAUGE THICKNESS |
| SUB-FRAME RAIL: | 9" HIGH X 3" X 1/4" THICKNESS |
| SUB-FRAME CROSS MEMBERS | 10 GAUGE |
| SUB-FRAME OUTRIGGERS: | 10 GAUGE |
| OUTRIGGER PADS: | 3/16" (3 PER SIDE, ENDS NOT PADDED) |

BAFFLES:

QTY: 3 AS REQUIRED. DISHED AND FLANGED, TOTAL CIRCUMFERENCE WELDED COMPLETE, COLLARED 18" MAN-WAYS STAGGERED FROM BAFFLE TO BAFFLE, EACH BAFFLE BOTTOM COLLARED HALF MOON PLUS (3) 4" VENT HOLES; ONE ON TOP, ONE ON EACH SIDE.

TANK DIMENSIONS:

OVAL: 58" X 94"
LENGTH: (SEAM TO SEAM) 284 1/4" (FRAME RAIL)

TUNNEL/WALKWAY:

AN EXTRUDED STEEL DOUBLE LEG TUNNEL 14 GAUGE STEEL DESIGNED TO MEET THE REQUIREMENTS OF THE TC406 CODE WILL RUN FULL LENGTH OF THE UNIT. THE WALKWAY INSIDE THE TUNNEL WILL BE DRAINED THROUGH 2" PVC DRAIN TUBES RUNNING EXTERNALLY DOWN THE FRONT OF THE TANK. NOTE: WALKWAY WILL BE EXPANDED STEEL MESH.

FENDERS:

END PLATED, RIBBED, 114" LONG X 14 GAUGE

LADDER:

STEEL PIPE MODEL C/W PLATFORM

PLATFORM:

INSTALLED, DRIVER'S SIDE – FRONT LOCATION, ONE PIECE FORMED WITH PAD.

VENT/OVERFLOW LINE:

3" X SCHEDULE 40 PIPE, LOCATED NEXT TO MANHOLE COVER WITH VIC COUPLER CONNECTION, EXTENDS TO REAR OF TANK BELOW TUNNEL LEVEL AND DOWN THE REAR OF TANK HEAD, ANGLED 10 DEGREES TO CURB SIDE, END FITTED WITH 3" GATE VALVE (COMPLIES WITH TC406 CRUDE)

FUSIBLE CAP:

2" NIPPLE WITH FUSIBLE CAP LOCATED BEHIND MANHOLE COVER.

MANHOLE COVER:

17" DIAMETER COVER COMPLETE WITH 10" FILL CAP. TIONA BETTS MODEL FVA 9416-BX-B LOCATED AT CENTER OF TANK.

SUMP:

10" DIAMETER, COMPLETE WITH 4 VIC GROOVED NIPPLE AND VIC VALVE

DRAIN:

6" NOZZLE C/W 6" AIR ACTUATED BUTTERFLY VALVE, 3" OUTLET TO GRAVITY FEED SPRAY BUMPER

MOUNTING TANK PACKAGE:

HARDWARE COMPLETE WITH BRACKETS, INCLUDED. NEOPRENE IS FULL LENGTH FROM FRONT OF TANK.

LIGHTING:

LED LIGHTING SYSTEM IN COMPLIANCE WITH THE REQUIREMENTS OF THE CANADIAN MOTOR VEHICLE SAFETY STANDARDS. TWO JUNCTION BOXES ATTACHED TO FRAME RAIL, D/S FRONT AND REAR CENTER C/W REMOVABLE CHECKER PLATED COSMETIC COVER. WIRING FULL LENGTH PROTECTED BY 1" X 19' LONG STEEL PIPING FITTED THROUGH CROSS MEMBERS OF THE SUB-FRAME.

FLOAT:

ADVANCE SIDECAN MODEL (RECESSED)

PUMP:

3" BOWIE C/W RUBBER GEARS

PUMP DRIVE:

HYDRAULICALLY DRIVEN BY AIR SHIFT PTO

BUMPER:

STANDARD SPRAY BUMPER C/W 3" CAMLOCK FITTING AND DUST CAP

CABINET:

STEEL BODY C/W HEATER AND LIGHT TO HOUSE PUMP

CALIBRATION/TESTING:

THIS UNIT WILL NOT BE CALIBRATED. UNIT WILL BE AIR TESTED FOR LEAKS DURING THE FINAL STAGE OF PRODUCTION USING ONE (1) P.S.I. TUNNEL AND THREE (3) P.S.I. TANK SHELL.

PAINT:

COMPLETE UNIT SANDBLASTED, PRIMED AND PAINTED WITH 2 COATS OF ENDURA PAINT.

EQUIPMENT WILL BE SUPPLIED AND INSTALLED ON A CUSTOMER SUPPLIED ROADWORTHY CHASSIS.

2008 VIP 125 BBL CRUDE TANK

OPTIONS AVAILABLE (EXTRA):

- TANK LINING
- DEVOE 253 FOR CRUDE
- EXTERIOR FOAM INSULATION

PRICE IS F.O.B. NISKU AND SHALL BE FIRM FOR A MINIMUM OF 30 DAYS. A 10% DEPOSIT WITH YOUR ACCEPTANCE OF OUR QUOTATION WILL COMMENCE MANUFACTURE, WITH BALANCE DUE ON DELIVERY.

PLEASE NOTE:

MANUFACTURER WILL PROVIDE WARRANTY ON ALL COMPONENTS FOR 12 MONTHS ON ALL MANUFACTURED COMPONENTS.

ALL WARRANTY IS SUBJECT TO MANUFACTURER'S APPROVAL. ALL WARRANTY WORK IS TO BE PERFORMED AT MANUFACTURER'S PREMISES, UNLESS OTHERWISE AUTHORIZED IN WRITING.

ALL NEW UNITS ARE TO BE PAID IN FULL PRIOR TO LEAVING MANUFACTURER'S PREMISES. INTEREST OF 1.5% WILL BE CHARGED ON ALL INVOICES OVER 30 DAYS.

ANY FRAMEWORK TO TRUCK MODIFICATIONS REQUIRED PRIOR TO JOB COMMENCEMENT WILL BE EXTRA. ANY OTHER CHANGES OR ADDITIONS TO THIS QUOTE WILL BE ADDED TO THE FINAL PRICE.

YOURS TRULY,

SALES ASSOCIATE
CAMEX EQUIPMENT SALES
& RENTALS INC.

ACCEPTANCE SIGNATURE

PLEASE PRINT NAME

DATE OF ACCEPTANCE